



ELEVATION
SCALE 1:10



SECTION
SCALE 1:10

GENERAL NOTES

- ENSURE THAT WORK IS IN ACCORDANCE WITH BRISBANE CITY COUNCIL ENVIRONMENTAL BEST PRACTICE NOTES.
- SITE SETOUT TO BE VERIFIED BY SUPERINTENDENT OR LANDSCAPE ARCHITECT PRIOR TO THE COMMENCEMENT OF CONSTRUCTION WORKS.
- VERIFY LOCATION OF ALL SERVICES AND EASEMENTS PRIOR TO THE COMMENCEMENT OF WORKS.
- WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DISTANCES.
- VERIFY ALL DIMENSIONS ON SITE PRIOR TO CONSTRUCTION.
- STRUCTURES HAVE BEEN DESIGNED ON THE ASSUMPTION THAT THE MINIMUM ALLOWABLE BEARING CAPACITY FOR SOIL IS 100KPA AND TERRAIN CATEGORY = 2.5.
- IN EACH CASE ENGINEERING CERTIFICATION AND MODIFICATION AS NECESSARY WILL BE REQUIRED FOR PARTICULAR SOIL AND SITE CONDITIONS.
- THE COPYRIGHT OF THIS DRAWING REMAINS THE PROPERTY OF THE BRISBANE CITY COUNCIL.
- DIMENSIONS IN MILLIMETRES (UNO).

FOOTINGS

AS DETAILED. CONCRETE TO BE N25, MAX AGGREGATE SIZE 20MM, MAXIMUM SLUMP 80MM.

TIMBER WORK

ALL TIMBER TO BE ACQ TREATED ROUGH SAWN SELECT GRADE HARDWOOD OF A SINGLE SPECIES.
ALL TIMBER IN CONTACT WITH GROUND TO BE PRESERVATIVE TREATED TO HAZARD CLASS H5 TO AS1604.1-2000 AND HAVE A DURABILITY CLASS 1 (IN GROUND) TO AS5604-2003.
ALL TIMBER TO BE FREE OF KNOTS, SPLINTERS, CRACKS OR ANY MAJOR DEFECT.
ALL EXPOSED EDGES TO BE ARRISSED 4MM.
POSTS TO BE 100X50MM WITH CHAMFERED TOPS
SIGN BOARDS TO BE 150X50MM.

SIGN BOARDS

SIGN BOARDS TO BE ROUTED TIMBER TO SIZES SHOWN. REFER TO BSD-10511-DESCRIPTIVE SIGN-NATURAL AREA-SHEET 3 OF 3-NAME LAYOUT FOR ROUTING OF LETTERING.

FIXINGS

ALL FIXINGS TO BE STAINLESS STEEL.
SIGN BOARDS - TO BE FIXED TO POSTS WITH 14 GAUGE CLASS 3 BATTEN SCREWS, RECESSED ON FRONT, 2 NO. PER POINT OF FIXING

FINISHES

TIMBER TO BE PRIMED AND THEN FINISHED WITH MINIMUM 2 NO. COATS OF DULUX 'PINE NEEDLE' COLOUR.
COLOUR SELECTION IN ACCORDANCE WITH THE NATURAL AREAS DESIGN MANUAL COLOUR SCHEDULE.

ISSUE	AMENDMENT	DRAWN DATE	CHK'D DATE	APPR'D DATE
A	ORIGINAL ISSUE	DEC '14	DEC '14	DEC '14

DRAWING AUTHORISED FOR PUBLICATION			
DESIGN	CPO - P&D	DATE	DEC '14
DRAWN	CPO - P&D	DATE	DEC '14
CHECKED	BI - FSG - AS	DATE	DEC '14
DRAWING FILENAME	BSD-10516.dwg		
ASSOCIATED PLANS			

SENIOR CO-ORDINATOR NATURAL ENVIRONMENT
 ASSET SERVICES/BRISBANE INFRASTRUCTURE



BRISBANE CITY COUNCIL STANDARD DRAWING	
ADVISORY SIGN - NATURAL AREA - DIRECTIONAL	SCALE AS SHOWN DWG No. BSD-10516 ORIGINAL SIZE A3 REVISION A