


REFER TO BSD-9061 AND BSD-9062
FOR ADDITIONAL SPECIFICATION
NOTES & DETAILS



DECO PATH - SECTION

GENERAL NOTES & SPECIFICATION

- G1. MATERIAL CHOICES ARE TO BE DETERMINED ON THE GROUNDS OF SUSTAINABILITY, LOW MAINTENANCE, VANDAL RESISTANCE, PRODUCT AVAILABILITY AND SUITABILITY TO THE CLIMATIC CONDITIONS. MATERIALS ARE TO BE LOCALLY SOURCED.
- G2. ENSURE MOWN HEIGHT OF GRASS (TURF) FINISHES FLUSH WITH PATH EDGE.
- G3. ENSURE GARDEN AREAS (MULCH) FINISH 25mm BELOW ADJACENT PATH EDGE.
- G4. ENSURE EVEN GRADE CROSSFALL MIN. 1:50 TO PATH.
- G5. ENSURE DECO PATHS ARE LOCATED IN ACCORDANCE WITH DETAILED LANDSCAPE PLAN AND PARKS CHAPTER OF INFRASTRUCTURE DESIGN PLANNING SCHEME POLICY.
- G6. AUSTRALIAN STANDARDS SHALL BE IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE REFERENCED AUSTRALIAN STANDARDS EXCEPT WHERE VARIED BY SPECIFICATIONS AND/OR DRAWINGS.
- G7. FOR SLIP RESISTANCE REQUIREMENTS, REFER "REFERENCE SPECIFICATIONS FOR CIVIL ENGINEERING WORK" - S150 ROADWORKS.
- G8. REFER TO THE BRISBANE ACCESS AND INCLUSION PLAN 2012-2017 FOR FURTHER INFORMATION WHEN PLANNING AND DESIGNING THE BUILT ENVIRONMENT TO REASONABLY CONSIDER ACCESS AND INCLUSION FOR ALL WHERE APPROPRIATE.
- G9. ALL DIMENSIONS IN MILLIMETRES (U.N.O.).

COMPACTION

- C1. COMPACT SUBBASE AND DECO MATERIAL SEPARATELY NOT LESS THAN 95% MAXIMUM DRY DENSITY AS DETERMINED BY THE MODIFIED COMPACTION TEST AS DEFINED IN AS1289 FOR THE UPPER 150mm. AVOID COMPACTION AROUND THE BASE OF EXISTING AND PROPOSED TREES.

SUBBASE PREPARATION

- SB1. ENSURE SUBBASE PROFILE FORMS THE REQUIRED DRAINAGE FALLS WHEN THE SURFACE IS LAID.

SURFACE CONSTRUCTION

- SC1. THE FOLLOWING STEPS ARE SUGGESTED AND WILL NEED TO BE REPEATED TO ACHIEVE THE FSL:
 - PLACE AND RAKE EVENLY APPROXIMATELY 30mm OF DECOMPOSED GRANITE MATERIAL.
 - ADD SOIL STABILISER DUSTAC OR SOILTAC (OR APPROVED EQUIVALENT) AT A RATE RECOMMENDED BY MANUFACTURER ALTERNATIVELY RAKE THROUGH CEMENT AT 5% RATIO.
 - MOISTEN THE MATERIAL AND COMPACT USING A VIBRATING ROLLER. THE ROLLER SHOULD NOT WEIGH MORE THAN 30KG.
- SC2. THE FINISHED SURFACE SHALL BE FREE FROM STONES EXCEEDING 20mm IN DIAMETER AND SHALL REMAIN FREE OF RUTS, SUBSIDENCE AND LACK OF COHESION.
- SC3. IF AT TIME OF CONSTRUCTION, THE SUB-GRADE STRENGTH IS SUCH THAT IT IS PENETRATING / INFILTRATING THE CLASS 2 GRAVEL LAYER DURING COMPACTION, A B.C.C. TYPE 3 GEOTEXTILE IS TO BE PLACED BETWEEN THE GRAVEL AND THE SUB-GRADE.

THE PURPOSE OF THIS STANDARD DRAWING IS TO PROVIDE TYPICAL DETAILS THAT SUPPORT THE DESIRED OUTCOMES OF THE BRISBANE CITY PLAN 2014 AND ASSOCIATED PLANNING SCHEME POLICIES. THE FITNESS FOR PURPOSE OF THIS STANDARD DRAWING FOR A SPECIFIC PROJECT SHOULD BE ASSESSED AND ACCEPTED BY AN APPROPRIATELY QUALIFIED DESIGNER AND/OR REGISTERED PROFESSIONAL ENGINEER OF QUEENSLAND (RPEQ).



BRISBANE CITY COUNCIL STANDARD DRAWING

PATH - DECO

PUBLISH DATE		SEP 2024
SCALE		NOT TO SCALE
DRAWING NUMBER		BSD-5213
ORIGINAL SIZE	REVISION	
A3	B	